Components List for Fibre Optic Cable Through And Local Joint

Item No.	Qty.	Description	Possible Supplier	Part No.
1	1	Cabinet	TSS Stores Yate	HA Type 609D
3a	2	Enclosure, Lid and Fixing Brackets	Klochner–Moeller Unit 1 New Town Rd. Salisbury Wilts.	U–C143X–125
3b	2	Backplate With 4mm Fixing Screws	Klochner–Moeller Unit 1 New Town Rd. Salisbury Wilts.	M3–143
3c	2	Laser Warning Symbol to BS 5378		
4	1	Cassette Assembly & Rivets	BICC C&E Div. Helsby Cheshire	CSB–1601–A
5	16	Self adhesive Plastic Saddles	R–S Components PO Box 99 Corby Northants	543–478
6	12	Splice Protector as Fibre Colour	Majortec, Netly Firs, Kanes Lane, Bittern, Southampton	FOJ 500 2A
7a	36	0.7mm PTFE Tubing as Fibre Colour		TWT 28A
7b	3 Sets	Collets Numbered 0–9	R–S Components PO Box 99 Corby Northants	554–*** Size C
8	36	Rubber Sleeves (see text sheet 3)	R–S Components (cable 357–817 with conductor removed)	357–817
9	4	Heatshrink Gland	Sigmaform, Sywell Rd. Park Farm Ind. Est. Northants.	CES 2A/25mm
10a	3	75mm Sleeving on Soldered Pairs		
10b	2	Saddle Clips	Richco West St. Erith Kent	LWS–3–01
11a	1 Pack	Cable Ties for Copper Pairs	R–S Components PO Box 99 Corby Northants	
11b	36	Cable Markers	Hellermann Ltd	Helvin P55
12	2	Enclosure, Lid and Fixing Brackets	Klochner–Moeller Unit 1 New Town Rd. Salisbury Wilts.	U–C123X–125
13a	4	Terminal Blocks	Klippon Elect. Power Station Rd. Sheerness Kent	BK12 062532
13b	4	Terminal Blocks	Klippon Elect. Power Station Rd. Sheerness Kent	BK6 062522
14	2.5 Mtr	0.9 Sq mm Jumper Wire		
15	4	Alloy Bracket to sheet 3 Det 'C'		
16	2	Bakelite Mounting Plate to sheet 3 Det 'C'		
17	4	30mm x M6 Stainless Screw Nut & Washer		
18	3	Heatshrink Gland	Sigmaform, Sywell Rd. Park Farm Ind. Est. Northants.	CES 3FR
19	1	Backboard 310x840x12mm to sheet 3 Det 'D'	Part of Cabinet 609D	
20	2	Glandplate to sheet 3 Det 'B'		
21	4	50mm x M8 Stainless Screw Nut & Washer	Part of Cabinet 609D	
22	3	Brass Gland & Earth Tag to BS6121	CMP Ltd St. Peters Newcastle on Tyne/BICC	40–EIW
23a	3	10 Sq mm Earth Wire & Crimped Lugs		
23b	3	25mm x M10 Brass Screw Nut & Washer		
24	1	Cabinet Earth Bolt	Part of Cabinet 609 D	
25	3	Cable Ident Marker	Critchley Ltd Brinscombe, Stroud, Glos.	'K' Type
26		Fibre Optic Cable to HA Spec TR2017	TSS Stores Yate	
27	4	Dessicant Pack With Colour Identification	Mineral Derivatives, 217 Wellington Rd. Stockport Cheshire	
28	200mm	25mm Flexable Plastic Conduit		
29	2	25mm Plastic Conduit Glands		
30	1	25mm x 47mm Conduit Nipple (Plastic/Galv)		
31	2	25mm Bushes (Plastic/Brass)		
32	2	25mm I/D Polythene Washers		
34	12	20mm x M2.5 Stainless Screw Nut & Washer	See sheet 3 Detail "C"	
35	4	30mm x M2.5 Stainless Screw Nut & Washer		
36	4	10mm x M2.5 Stainless C/S Screw Nut & Washer		
37	8	12mm X M4 Stainless S/T Screw		

A complete kit of parts may be obtained from;
Cable Link, Unit 22 Cheney Manor Industrial Estate Swindon
Mainland Communications Ltd. 8 Metro Centre Springfield Road
Hayes Middlesex.

ISSUE	AMENDMENTS	APPD/DATE
A	FOR CONSTRUCTION	BD 09/02/03
I	FIRST ISSUE	BD 19/07/02

This drawing was generated on computer and must not be manually updated

SCOTTISH EXECUTIVE
Traffic Controller Unit,
EDINBURGH, EH6 6QQ
NADICS
www.nadics.org.uk

TITLE OF CABLE CASSETTE TERMINATION THROUGH ARRANGEMENT IN HA TYPE 609 CABINET – L

ORIGINAL DRAWING SIZE: 297 x 420
ALL DIMENSIONS ARE IN MM
TOLERANCE ±1 UNLESS OTHERWISE STATED
THIRD ANGLE PROJECTION DO NOT SCALE

DRN C.S.G. DATE 15.07.02
CHKD B.D. DATE 19.07.02
DRG. NO. NDX1034-02dt
SCALE N.T.S.
SHT. NO. 4 of 6